Rig #15 Specifications

Drilling Range:	10,000' With 4-½" Drill Pipe 12,000' With 3-½" Drill Pipe
Drawworks:	RG JC 28B, 1,000 HP
Mast:	RG JJ18038 125' Telescoping Double Mast 396,000 lbs Static Hook Load With 10 Lines
Substructure:	RG 20' High 396,000 lbs Capacity
Mud Pumps:	(2) Weatherford MP-10 Triplex, 10"x 6-¾", 1,000 HP
Rotary Table:	RG 27-1/2"
Automatic Catwalk	Canrig Powercat Model 3000
Traveling Assembly:	RG YG225 5 Sheave, 250 Ton Block/Hook and RG 250 Ton Swivel
Generators:	(2) 490 HP Diesel Engines with 300 kW Generators, CARB Compliant
Mud System:	(1) Pit System, 400 Total Barrels NOV Brandt Shakers
BOPE:	RG GK 11-5M Annular, RG 11-5M Double Gate RG 120 Gallon Accumulator 5,000 psi Choke Manifold
Water/Fuel Storage:	400 BBLS/3,000 Gallons
Auxiliary Equipment:	(2) Hydraulic Winches Wireline Unit (.092") (2) Air Compressors Crew Doghouse Toolpusher Trailer