Rig #44 Specifications

Drilling Range:	14,000' with 4-½" Drill Pipe
Drawworks:	Superior 1,000 UE, 1,000 HP
Mast:	Dreco 133' High Free Standing, 521,000 lbs Static Hook Capacity with 10 Lines
Substructure:	Dreco 21' High Slingshot 525,000 lbs Casing and 325,000 lbs Setback
Mud Pumps:	(2) Weatherford F-1,600, 7"x 12", 1,600 HP, 5,000 PSI
Rotary Table:	Sentry 27 ½"
Automatic Catwalk:	Canrig Powercat Model 3000 Automatic Catwalk
Floorhand:	Blohm and Voss FH-80
Traveling Assembly:	Canrig 275 Ton 5 Sheave Block
Top Drive:	Canrig Model 6027 AC 275 Ton Top Drive 30,000 ft-lb torque @ 110 RPM
Generator Sets:	(3) 1,354 BHP Diesel Engines with 1,225 kW Generators
SCR/Power System:	NOV 4 Bridge SCR
Mud System:	(2) Pit System, 1,100 Total Barrels (1) 220 bbl Pre-Mix (2) Brandt King Cobra Shale Shakers Poor Boy Gas Buster
BOPE:	13 5/8" 5,000 PSI Annular, 13 5/8" 5,000 PSI Double Ram 5,000 PSI Choke Manifold 160-gallon 6 Station Accumulator
Water/Fuel Storage:	400 bbls/12,300 Gallons
Auxiliary Equipment:	(2) Air Winches Crew Change House Rig Manager House