Rig #19 Specifications

Drilling Range:	28,500 with 5" Drill pipe
Drawworks:	American Block 1500 HP
Mast:	NOV 142' High 750,000 lbs Static Hook Capacity with 10 lines
Substructure:	NOV Slingshot 28' High 750,000 lbs Casing and 576,000 lbs Setback NOV Steel Toe 1200 Walking system
Mud Pumps:	(3) FB-1600 Triplex, 7"x 12", 1,600 HP, 7,500 PSI
Rotary Table:	NOV 37 1/2" Hydraulic Drive
Automatic Catwalk:	NOV PC-5-47 PipeCat
Floorhand:	Blohm and Voss FH-80
Traveling Assembly:	NOV 6 Sheave 500 Ton
Top Drive:	NOV TDS-11SA 500 Ton 37,500 ft-lb torque @ 110 RPM
Generators:	(4) 1,476 BHP Diesel Engines with 1,225 kW Generators
AC/VFD House:	IDE 4X5 VFD Power System Auto Drill, Bridge and Overpull Protection
Mud System:	(2) Pit System, 1,000 Total Barrels (3) Mi Swaco Mongoose Pro Flow Line Cleaners (1) 220 bbl Pre-Mix
BOPE:	13 5/8" 5,000 PSI Annular, 13 5/8" 10,000 PSI Double Ram and Single Ram 10,000 PSI Choke Manifold 300 Gallon Accumulator Poor Boy Gas Buster NOV BOP Transporter
Water/Fuel Storage:	900 BBLS/17,000 Gallons
Auxiliary Equipment:	(2) Air compressors Crew Change House Rig Manager House